



Never Perform an Intake Service Through the Throttle Body on Any Vehicle with Drive-by-Wire

COMPLAINT: Possible problem with the drive-by-wire system after a fuel system service.

CAUSE: Cleaner entering the drive-by-wire sensors or motors.

CORRECTION: Never perform any throttle body or intake cleaning service that requires spraying the cleaner through the throttle body on a car equipped with a drive-by-wire system.

This means don't spray the TBC cleaner through the throttle body, and don't use the BLAST intake cleaning tool with the S-nozzle device.

Always clean the throttle and throttle body using a small amount of TBC sprayed on a clean shop towel, as explained in CSTB0008.

And always perform the intake cleaning service through a manifold vacuum port, as close to the throttle body as possible.